3	KSRRB M500-15: Providing, laying and rolling with vibratory roller of built-up spray grout layer over prepared base consisting of a two layer composite construction of compacted crushed coarse aggregates using motor grader for aggregates. Key stone chips spreader may be used with application of bituminous binder after each layer, and with key aggregates placed on top of the second layer to serve as a base confirming to the line, grades and cross-section specified, the compacted layer thickness being 75mm Complete as per specifications. MORTH specification No. 506 **Page No.177/ Item No. 21.16/ PWD SR 2013-14**	**Sqm**							
	19th Cross roads		1	120.00	1.00		120.00		
	12th cross		1	130.00	1.00		130.00		
	20th cross		1	1020.00	1.00		1020.00		
						Total	**1270.00**	**268.92**	**341528.0**
	Basic Rate	249.00							
	Area Weightage 8%	19.92							
	Total	**268.92**							
4	KSRRB 500-7: Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 **Page No. 176/ Item No. 21.8/ PWD SR 2013-14**	**Sqm**							
	19th Cross roads		1	120.00	1.00		120.00		
	12th cross		1	130.00	1.00		130.00		
	20th cross & Cross roads		1	1020.00	1.00		1020.00		
	Basic Rate	20.10					**1270.00**	**21.71**	**27572.0**
	Area Weightage 8%	1.61							
	Total	**21.71**							
5	KSRRB M500-17: Providing and laying **semi dense bituminous concrete 25mm thick** with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen using 40-60 HMP using Mechanical paver **Page No. 178/ Item No. 21.20.5/ PWD SR 2013-14**	**Cum**							
	19th Cross roads		1	120.00	3.00	0.025	9.00		
	12th cross		1	130.00	3.00	0.025	9.75		
	20th cross		1	1020.00	3.00	0.025	76.50		
	Ugd line		1	120.00	1.00	0.025	3.00		
			1	130.00	1.00	0.025	3.25		
			1	1020.00	1.00	0.025	25.50		
	Basic Rate	9069.00					**95.25**	**9794.52**	**932928.0**
	Area Weightage 8%	725.52							